SHED

JOE DODGE CENTER

PATCH & REPAIR ENTIRE CATCH BASIN

GRANITE CURB FLUSH W/ ASPHALT & GRAVEL

TOPSOIL & SEED

PROVIDE 6" COMPACTED CRUSHED AGGREGATE TRAIL

WALL SECTION TO BE REMOVED

PATCH & REPAIR ENTIRE CATCH BASIN

INSTALL 42 L.F. OF 15" PE PIPE

TOPSOIL & SEED

ADDITIONAL SNOW STORAGE

AGE WITH 15" PE PIPE 156 L.F.

3+00

PT = 3+32.56

TAPER GRANITE CURB FROM FLUSH TO 4" VERTICAL HEIGHT

4+00

PATCH & REPAIR ENTIRE CATCH BASIN

TRADING POST

REPLACE THREE RAILINGS W / RAILINGS THAT MEET ADA/ABA

REPLACE WITH 15" PE PIPE 90 L.F.

EDGE OF EXISTING PARKING

TOPSOIL & SEED

3' FLUSH CURB CUT FOR DRAINAGE

5+00

CURB LENGTH DEPENDENT ON TANK DEPTH

TAPER CURB FROM FLUSH TO 4" VERTICAL HEIGHT

PATCH & REPAIR ENTIRE CATCH BASIN

4" HIGH VERTICAL GRANITE CURB

TANK

REPLACE WITH 15" PE PIPE 80 L.F.

6+00

Rocky Area

AREA OF EXCAVATION SEE GENERAL NOTES

TOPSOIL & SEED

CURB CUT

GRANITE CURB AT 45° ANGLE

INSTALL FLAGPOLE

TOPSOIL & SEED

30' OFFSET LINE FROM TRAVELWAY BREAK AWAY ZONE

RECONSTRUCT SIGN

STOP

7+00 Old Route 16

GRANITE CURB FLUSH W/ ASPHALT & GRAVEL

PC = 7+93.19

TAPER FROM FLUSH TO 4" VERTICAL HEIGHT - BOTH LANES

KEEP RIGHT

NEW ASPHALT PAVEMENT

TOPSOIL & SEED

ADDITIONAL SNOW STORAGE

8+00

PT = 8+56.21

PATCH & REP ENTIRE CATCH

Jackson

NH–16

Gorham

EDGE OF EXISTING PARKING

4" VERTICAL GRANITE CURB SEE GENERAL NOTES

REPLACE WITH 15" PE PIPE 65 L.F.

9+

True

GRAPHIC SCALE

20 0 10 20 40 80

( IN FEET )

1 inch = 20 ft.

LEGEND

- TREE
- FENCE
- U-POLE
- SIGN
- MANHOLE COVER
- CULVERT OUTLET
- HYDRANT
- ROCK / BOULDER
- ROCK WALL
- SIDEWALK
- INSTALL SIGN
- GRANITE CURB
- ASPHALT PAVEMENT
- 8 X 8 WOOD BOLLARD

**General Notes**

PARKING LOT CROSS SLOPE SHALL BE -3% FROM WEST TO EAST

ENTRANCE LANES SHALL BE OUTSLOPED 2%

MAINTAIN EXISTING GRADE AT MANHOLE COVERS AND CATCH BASIN GRATES

EAST GRANITE CURB SHALL HAVE CURB CUTS APPROXIMATELY EVERY 50' TO PROVIDE DRAINAGE

AREA OF EXCAVATION FOR SIDEWALK SHALL BE SLOPED BACK AT 2:1. EXCAVATED MATERIAL SHALL BE USED AS FILL AT THE BACK FACE OF THE GRANITE CURB ON THE EAST SIDE OF THE PARKING AREA

SEED ALL DISTURBED AREAS

| No. | Revision/Issue | Date |
|---|---|---|
| 4 | | |
| 3 | | |
| 2 | | |
| 1 | | |

U.S. DEPARTMENT OF AGRICULTURE
FOREST SERVICE
Region 9
EASTERN REGION

Project Name
Pinkham Notch Visitor Center Parking Lot Reconstruction
WHITE MOUNTAIN NATIONAL FOREST
ANDROSCOGGIN RANGER DISTRICT

Forest Contact
Jay Sylvester
1-603-447-5448 X135

Drawing Title
ENLARGED ENTRANCE PLAN

| | |
|---|---|
| Drawn: Rory Shea | Project |
| Checked: Jay Sylvester, Ken Allen | Drawing No. C-401 |
| CAD File No. | |
| Date: June 2008 | |
| Scale: 1" = 20' | Sheet 8 of 12 |